



NOTES:

1. SEWER LATERAL AND CLEANOUT PIPING SHALL BE PER APPROVED MATERIALS LIST. SEWER LATERAL FITTINGS SHALL BE OF SAME MATERIAL AS THE SEWER LATERAL PIPE.
2. ALL MAIN LINE TAPS ON EXISTING ACTIVE MAINS SHALL BE MADE BY THE PSA OR A PSA APPROVED CONTRACTOR.
3. PIPING ON PRIVATE SIDE OF CLEANOUT TO BE INSTALLED PER GOVERNING JURISDICTION REQUIREMENTS.
4. THIS DETAIL IS FOR TWO CONNECTIONS TO A SINGLE 6" CLEANOUT. THREE OR MORE RESIDENTIAL CONNECTIONS SHALL BE MADE VIA A MAIN SEWER LINE EXTENSION.
5. SEWER CLEANOUTS SHALL BE PER CLEANOUT DETAILS.
6. DEPTH RESTRICTIONS, CLEARANCES, AND SEWER LATERAL PROFILES ARE TO FOLLOW THE SEWER LATERAL DETAILS.
7. FOR NEWLY DEVELOPED STRUCTURES AND LINES, LOWEST SERVED FINISHED FLOOR ELEVATION SHALL BE A MINIMUM OF THREE FEET (3') ABOVE THE TOP OF THE MAIN AT THE POINT WHERE THE SERVICE LATERAL CONNECTS TO THE MAIN.
8. IN CASES WHERE THE SEWER LINE AND/OR THE STRUCTURE IS ALREADY SET, THE GRADE SHALL BE EVALUATED TO ENSURE THAT THE LOWEST SERVED FINISHED FLOOR CAN FLOW BY GRAVITY. IN CASES WHERE THIS IS NOT POSSIBLE, THE PROPERTY OWNER SHALL BE RESPONSIBLE FOR INSTALLING A GRINDER PUMP AS REQUIRED.
9. CONNECTION TO EXISTING LATERALS SHALL BE MADE USING FLEXIBLE COUPLINGS PER APPROVED MATERIALS LIST.
10. MARKING TAPE AND TRACER WIRE ARE TO BE PLACED ALONG ALL SEWER LATERALS.



# MULTI-UNIT 6" SEWER SERVICE CONNECTION

EFFECTIVE  
05/2023

DETAIL NO.  
310